Fenwick Air Systems Ltd

RISK ASSESSMENT AND METHOD STATEMENT

Installation of ductwork at high level

Project	Quayside House, Level 3 office fit-out
Location of works	Quayside House, 40 Dock Street, Northbridge NB1 7HS - Level 3 open plan and riser 2
Document reference	FAS-RAMS-014
Activity	Installation of supply and extract ductwork, supports and fire dampers above the ceiling grid
Programme	Start 9 November 2026, duration 4 weeks, Monday to Friday 07:30 to 17:00
Prepared by	Lena Marsh, Contracts Manager
Approved by	Owen Pryce, H&S; Manager

Revision history

Rev	Date	Description	Prepared by	Approved by
A	12/10/2026	First issue for comment	L. Marsh	O. Pryce
B	26/10/2026	Main contractor comments: rescue plan, briefing	L. Marsh	O. Pryce

1. SCOPE AND SEQUENCE OF WORKS

Scope of works *Describe the work to be carried out and where.*	Install galvanised supply and extract ductwork (approx. 220 m), threaded rod supports, 14 fire dampers and 36 grilles above the suspended ceiling grid on Level 3, and connect to the risers.
Sequence *Set out the work step by step.*	1. Set out support positions from the coordinated drawings and mark the soffit. 2. Drill and fix anchors with on-tool dust extraction, install drop rods and unistrut. 3. Lift duct sections with a material hoist and fix to supports from podium steps or MEWP. 4. Install fire dampers in the riser walls, seal joints, pressure test and label.
Access and egress *How will operatives reach and leave the work area?*	Access via the main core stair and goods lift to Level 3. Work area segregated with barriers and signage; walkways kept clear to the fire exits in core A and core B.

2. PEOPLE

Supervisor *Who is in charge of the work on site?*	Site supervisor: Callum Reid (SSSTS, first aid at work), on site full time.
Competence *What training and cards do the operatives hold?*	All operatives hold CSCS cards (ductwork installer, blue skilled worker). MEWP operators hold IPAF 3a/3b; two operatives hold PASMA for the mobile tower. Fire damper installers trained by the damper manufacturer (certificates in appendix C).
Briefing *How will the RAMS be communicated to the workforce?*	The supervisor briefs this RAMS to every operative before starting; each signs the briefing record. Daily start-of-shift briefing on the work area, permits and changes to the sequence. Operatives with limited English are briefed with a translated summary and a team leader who speaks their language.

3. EQUIPMENT AND MATERIALS

PPE *List the PPE required for this task.*	Safety helmet to EN 397 with chin strap when working from the MEWP. Safety boots S3, hi-vis vest, cut-resistant gloves level C (EN 388). Safety glasses EN 166, FFP3 disposable mask (face-fit tested) when drilling concrete.
Plant and equipment *List plant, tools and access equipment and their inspection.*	Scissor lift MEWP (Genie GS-1932 or similar): LOLER certificate, daily pre-use check. Podium steps and one mobile aluminium tower: weekly inspection, tagged. 110 V drills with on-tool extraction, PAT tested; material hoist with valid LOLER thorough examination.
COSHH *List hazardous substances and attach COSHH assessments.*	Duct sealant (water based): COSHH assessment CA-031 and safety data sheet attached. Fire-rated mastic for damper installation: COSHH assessment CA-044 and safety data sheet attached. Concrete dust from drilling: controlled by on-tool extraction and FFP3 masks.
Storage, housekeeping and waste *How will materials and waste be managed?*	Duct sections delivered just in time and stored in the agreed laydown area on Level 3. Work area cleaned at the end of each shift; offcuts segregated into the metal skip. Packaging returned to the supplier; dust controlled by extraction, no dry sweeping.
Permits *Which permits to work are needed?*	Hot works permit from the main contractor for any cutting in the riser (none planned). Permit to work at height on the MEWP issued daily by the main contractor site manager.

4. EMERGENCY, MONITORING AND HEALTH

Emergency arrangements *Describe the site emergency procedures.*	On the fire alarm, stop work, lower the MEWP and leave by the nearest protected stair. Assembly point: Dock Street car park, point B. First aiders: Callum Reid and the main contractor's site team; first aid kit in the site office. MEWP rescue plan: ground-level controls operated by a trained second person (appendix D).
Monitoring *How will the safe system of work be monitored?*	Callum Reid checks the work area and MEWP daily and records it in the daily diary. Contracts manager inspection every two weeks; RAMS reviewed if the scope or sequence changes.
Occupational health *Which health risks apply and how are they controlled?*	Noise from drilling: low-noise drills, hearing protection in the marked zone. Hand-arm vibration: drilling limited to 60 minutes per operative per day (below the exposure action value of 100 points). Manual handling: duct sections over 20 kg lifted with the material hoist; health surveillance for drilling operatives.

RISK ASSESSMENT

Task	Ductwork installation at high level	**Assessment no.**	FAS-RA-014
Assessed by	Lena Marsh	**Date**	26/10/2026
Review date	Start of works or any change of scope	**Location**	Quayside House, Level 3

Persons at risk (tick all that apply)	[X] Own operatives [X] Other trades [ ] Client staff [X] Visitors [ ] Members of the public

Activity / hazard	Risk	L	S	R	Control measures	Residual
Work at height from MEWP	Fall from platform, operative injured	3	5	15	Trained IPAF operators only; harness with short lanyard on boom lifts; guardrails closed; floor checked for loading and openings; exclusion zone below.	Low (5)
Falling objects	Tools or duct sections fall on people below	3	4	12	Exclusion zone with barriers and signs; tool lanyards; duct secured before release.	Low (4)
Drilling concrete soffit	Silica dust inhaled	4	4	16	On-tool extraction (M-class), FFP3 masks face-fit tested, no dry sweeping.	Low (6)
Hand-arm vibration from drills	HAVS	3	3	9	Low-vibration drills, trigger time recorded, rotation of tasks, exposure kept below 100 points.	Low (3)
Manual handling of duct sections	Back injury	3	3	9	Material hoist for sections over 20 kg, two-person lifts, trolleys on the floor.	Low (3)
Noise	Hearing damage	3	3	9	Low-noise tools; hearing protection zone above 80 dB(A); daily exposure checked.	Low (3)
Use of 110 V power tools	Electric shock	2	4	8	110 V CTE supply, PAT tested tools, leads routed off the floor.	Low (2)
Hot works in riser (if needed)	Fire	2	5	10	Hot works permit, fire watch 60 minutes after work, extinguisher at the work area.	Low (4)

L = likelihood, S = severity (1 to 5), R = L x S. 1-6 low, 8-12 medium, 15-25 high.

Emergency: MEWP rescue by ground controls (trained second person on every shift); fire alarm procedure and assembly point as section 4; spill kit for sealant in the site store.

BRIEFING RECORD

I confirm that the contents of this RAMS have been explained to me and that I understand them.

Name	Company	Card / qualification	Signature	Date
Callum Reid	Fenwick Air Systems	CSCS, SSSTS, IPAF 3a/3b		09/11/2026
Tomasz Wrona	Fenwick Air Systems	CSCS, IPAF 3a/3b		09/11/2026
Dev Malhotra	Fenwick Air Systems	CSCS, PASMA		09/11/2026